
# Diploma template | A5

Blue: bleed | Red: trim | Green: safe area



**FINISHED 148 x 210 mm | WITH BLEED 152 x 214 mm**

Full-scale guide (100%). Remove colored guides before submitting final artwork.

# Template lines & artwork preparation

Diploma printing | A5 portrait

**FINISHED 148 x 210 mm | WITH BLEED 152 x 214 mm**

## UNDERSTANDING THE COLORED LINES



### BLUE LINE

**Artwork size / bleed boundary**


Extend all backgrounds and edge-to-edge images to this line.



### RED LINE

**Trim line**

The final size of your diploma after trimming.



### GREEN LINE

**Safe area**

Keep text, names, logos, and other important details inside this line.

## ARTWORK PREPARATION

- Work at 100% scale. A5 finished: 148 x 210 mm; artwork: 152 x 214 mm.
- Use 2 mm bleed on every side and keep important content at least 5 mm from trim.
- Use CMYK color, 300 dpi images at final size, and embedded or outlined fonts.
- For double-sided printing, provide separate artwork for the front and back.
- Check spelling, names, and dates before submitting your files.
- Export a print-ready PDF without colored guide lines or instruction layers.

### IMPORTANT

If the artwork has no bleed, white edges may appear after trimming. Use the correct template for your chosen size.